



John E. Campo, Architect
105 Ducayet Dr.
Destrehan, LA 70047
(985) 764-8959

Campo Design
ARCHITECTS

GENERAL NOTES

- A. SITE INFORMATION SHOWN ON FIRST FLOOR PLAN (SHEET A03) IS PART OF BASE BID AND MAY NOT APPEAR ON CML SHEETS, BUT IS STILL PART OF CONTRACTOR'S RESPONSIBILITY. COORDINATE ALL SITE WORK ON BOTH CIVIL AND ARCHITECTURAL SHEETS.
- B. FOR PARTITION TYPES, SEE SHEET A25. FOR OPENING SCHEDULE, SEE SHEETS A26.
- C. VERIFY ALL DIMENSIONS NOTED CLEAR, HOLD OR MINIMUM DURING LAYOUT OF WORK. NOTIFY ARCHITECT OF DISCREPANCIES PRIOR TO PROCEEDING.
- D. MAINTAIN A MINIMUM OF 3'-6" CLEARANCE AT ALL EGRESS CORRIDORS.
- E. PROVIDE MTL. BACKING PLATES OR SOLID FIRE TREATED WD. BLOCKING IN ALL WALLS TO RECEIVE MLL/WORK OR OTHER WALL MOUNTED ITEMS. AS REQ'D BY EACH SPECIFIC ITEM.
- F. ALL PARTITION DIMENSIONS ARE TO FINISH SURFACE, UNLESS NOTED OTHERWISE. "ALIGN" SHALL MEAN TO ACCURATELY LOCATE FINISH SURFACES IN THE SAME PLANE.
- G. LOCATE ALL DOORS 4" FROM BACK OF DOOR FRAME (HINGE SIDE), TO END OF PARTITION IN WHICH DOOR IS LOCATED UNLESS NOTED OTHERWISE.
- H. SEE INTERIOR ELEVATIONS FOR TOILET ACCESSORY LOCATIONS.
- J. ALL WORK NOTED "BY OTHERS" OR "N/C" SHALL BE PROVIDED BY OWNER OR UNDER SEPARATE CONTRACT. INCLUDE SCHED. REQUIREMENTS FOR THIS WORK IN CONSTRUCTION SCHEDULE AND COORDINATE AS REQ'D TO ASSURE ORDERLY SEQUENCE OF INSTALLATION.

KEYNOTES

- 1 EXISTING FIRE EXTINGUISHER CABINET
- 2 DOWN SPOUT
- 3 REFRIGERATOR (N/C)
- 4 LINE OF ROOF ABOVE
- 5 RAMP. SEE CML FOR ELEVATIONS
- 6 NOT USED
- 7 NEW CONC. SIDEWALK
- 8 ELECTRIC DRINKING FOUNTAIN
- 9 NOT USED
- 10 FUTURE LOCKERS (N/C)
- 11 CLASS ROOM TV CABINET

LEGEND

- EXISTING (IN USE)
- EXISTING WALL CONSTRUCTION
- NEW WALL CONSTRUCTION

FIRST FLOOR AREA

TOTAL EDUCATIONAL AREA	- 7,281 SF.
SCHOOL OFFICES	- 1,520 SF.
TOTAL FIRST FLOOR AREA OF PHASE 2	- 8,781 SF.

